

**ZONE 7 WATER AGENCY
 2022-2023 STORM DAMAGE HIGH PRIORITY REPAIRS
 CALIFORNIA
 Project 307-24
 ADDENDUM NO. 1
 JUNE 26, 2024**

This Addendum No. 1 ("Addendum") is dated June 26, 2024, and modifies certain Bidding Documents issued by the Alameda County Flood Control and Water Conservation District, acting by and through its Zone 7 Water Agency ("District") in connection with the District's project: *2022-2023 Storm Damage High Priority Repairs*. All capitalized terms not otherwise defined herein shall have the meanings provided in the Bidding Documents. There are no other amendments to the Bidding Documents other than expressly contained in this Addendum No. 1. The bid submission date remains unchanged.

The following clarifications and/or modifications shall be incorporated into plans and specifications for the above-referenced project and shall become part of the Contract Documents. All other provisions and requirements shall remain unchanged.

CONTRACT DOCUMENTS AND SPECIFICATIONS

Addendum Item	Document/ Section	Location and Description of Change
1	Document 02240	<p>Modification to Document 02240-Temporary Water Diversion</p> <p>The first page of document 02240 (02240-1) was inadvertently omitted. The attached first page shall be included as part of the bid documents.</p>

Please be reminded that all bidders shall acknowledge receipt of this Addendum No. 1 in Document 00400 (Bid Form) and failure to acknowledge addendum in the Bid Form shall render the bid non-responsive and may be cause for its rejection.

Acknowledgement of receipt of Addendum No. 1 for the 2022-2023 Storm Damage High Priority Repairs, Project No 307-24.

Please also sign and email a copy of this page to Adolfo Perez, Zone 7 Water Agency, at aperez@zone7water.com to acknowledge receipt of Addendum No. 1 for this project.

**ZONE 7 WATER AGENCY
2022-2023 STORM DAMAGE HIGH PRIORITY REPAIRS
CALIFORNIA
Project 307-24
ADDENDUM NO. 1
JUNE 26, 2024**

Signature and Print Name

Date

Company

SECTION 02240 TEMPORARY WATER DIVERSION

PART 1 - GENERAL REQUIREMENTS

1.01 SCOPE OF WORK

- A. The work to be performed under this Section shall consist of furnishing all labor, materials, tools, transportation, supplies, equipment, appurtenances, fuel, and power, unless specifically excepted, necessary or required for any dewatering work required or as shown on the plans and described in these specifications. Work shall be in conformance to Caltrans standard specs Section 13 "Water Pollution Control".

1.02 DESCRIPTION OF WORK

- A. Water diversion will be implemented by the Contractor to maintain the work site as water-free as possible for the duration of in-channel work.
- B. Contractor shall utilize a temporary water diversion within the existing flood control channels using either
 - 1. Cofferdams at the upstream and downstream limits and bypass piping and/or pumps.
 - 2. Berms / Cofferdams to confine flow to one side of the channel, so work can occur at the toe of slope.

Dewatering shall be designed to minimize environmental impacts to the extent feasible. Dewatering shall be designed such that it does not cause damage or additional erosion or sedimentation to the surrounding channel.

1.03 REFERENCE SPECIFICATIONS

- A. 00700 General Conditions: Paragraph 15.2.E Adverse Weather Delays

PART 2 - CONSTRUCTION

2.01 COFFERDAMS

- A. For the purpose of this work, cofferdam shall be understood to mean any temporary type construction to satisfy the condition that all creek restoration work is to be done in the dry.